BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2019-20/OW/WORK_INDENT37091

APPROVED SCHEDULE - B

No.EE/BTP/BBMP/E-PMT/11/2019-20, Date: 11.07.2019

Name of Work:Construction of Temporary Emmersion Tank for Lord Ganesh in Ward No. 06 Thanisandra Byatarayanapura Sub Division.

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of "SHIVA KUMAR B S" ( )	
				In Figures	In Words
1	28.28	KSRB 2-1.1 : Earthwork in surface excavation in ordinary soil for levelling and lowering the ground manually (other than foundation of buildings, culverts, road drains and trenches of pipe lines and cables) and removing the excavated stuff to a distance not exceeding 50m and lift upto 1.5m, excavated surface levelled and neatly dressed, disposed earth to be levelled after breaking of clods and neatly dressed as per specifications. specification. No. KBS 2.1(a) / 2.3.1 Page No. 6 / Item No. 2.1 of PWD SR 2018-19	Cum	240.0	Rupees Two Hundred Forty Only
2	214.5	KSRRB 300-1. Earthwork excavation by manual means in ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5 m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete as per specifications. MORTH / Chapter 3 Page No. 143 / Item No. 19.1, PWD SR 2018-19 Up to 1.50 Mtrs Depth	Cum	120.0	Rupees One Hundred Twenty Only
3	214.5	above 1.50 Mtrs Depth	Cum	140.0	Rupees One Hundred Forty Only
4	945	Code 0516 - Providing Plastic Sheet (Page No. XXIX / I. 755 PWD SR 2018-19	Sqm	4.0	Rupees Four Only
5	165	Supply of water Through water Tank for filling Tank Hegadenagara	Each	310.0	Rupees Three Hundred Ten Only
6	165	Rachenahalli	Each	310.0	Rupees Three Hundred Ten Only
7	2.5	Providing Stone dust / Grit 4.75 mm to 0.075 mm to approach road and near immersion tank for levelling and to protect not to sliping Sl No. 45 Code 400 metal Component PWD SR Page No II PWD SR 2018-19 Rachenahalli Tank	Cum	850.0	Rupees Eight Hundred Fifty Only
8	2.5	Hegadenagara	Cum	850.0	Rupees Eight Hundred Fifty Only
9	66	Hire charge of pumping water 3.5 KL/hr capacity Pump Page No. L / Sl No. 49 PWD SR 2018-19 Hegadenagar	Hr	35.0	Rupees Thirty Five Only
10	66	Rachenahalli	Hr	35.0	Rupees Thirty Five Only
11	154	Providing Causal Labours (Unskilled mazdoor Heavy) (PWD SR 2018-19 Page No. LVI / I. 5) Hegadengara	No	380.0	Rupees Three Hundred Eighty Only
12	154	Rachenahalli	No	380.0	Rupees Three Hundred Eighty Only
13	1600	Providing erecting removing casurinapole barricading using poles of 7.50 to 10 cms, dia and 1.5 height above ground fixed vertically at intervals of 2.0 to 2.5 mtrs. C/C an horizontally at 0.50 mtr, above ground level, including fixing poles in the ground level for minimum depth of 3.0 mtr and tied with coir rope firmly including cost and conveyance of all materials, labour, lead and lift charges and complete on hire basis as per the engineer in charge.	Mtr	60.0	Rupees Sixty Only
14	3300	Hire Charge for Shamiyana with Necessary Bambo Poles, Erection Charges Including transportation - (Size: 40ft x 30ft = 1200 sqft) Hegadenagar	Sft	6.5	Rupees Six and Fifty Paise Only

Shivakumar B S

Sl. No	Approved Qty.	Description	Unit	Approved Tender Rates of "SHIVA KUMAR B S" ( )	
				In Figures	In Words
15	3300	Rachenahalli	Sft	6.5	Rupees Six and Fifty Paise Only
16	1650	Hire Charges for Shamiyana Side Wall of 8ft Hight (Size: 10x 15ft = 150 Rft) Hegadenagara	Rft	15.0	Rupees Fifteen Only
17	1650	Rachenahalli	Rft	15.0	Rupees Fifteen Only
18	110	Hire Charge for Armless Plastic Chairs Hegadenagara	No	4.0	Rupees Four Only
19	110	Rachenahalli	No	4.0	Rupees Four Only
20	55	Hire Charge for Wooden Table of Size 6ft x 2ft Hegade nagara	No	35.0	Rupees Thirty Five Only
21	55	Rachenahalli	No	35.0	Rupees Thirty Five Only
22	660	Hire Charge for supplying and running circuit service main with necessary messanger wire and reel insulators and maintaining the same 4 of 25 sqmm PVC insulated and sheathedaluminium wire (KPWD SR 2010-11 P.55/I.6 III b) hegadenagara	Mtr	8.0	Rupees Eight Only
23	660	Rachenahalli	Mtr	8.0	Rupees Eight Only
24	55	1321 Hire charge of 100 KVA Generator including operator, Fuel, transportation and Handling charges (PWD SR 2018-19 (P.LI / I.92) Hegadenagara	Hr	458.0	Rupees Four Hundred Fifty Eight Only
25	55	Rachenahalli	Hr	458.0	Rupees Four Hundred Fifty Eight Only
26	66	Hire charges for Flood lighting arrangements for the stage and existing immersion Tank during night time Hegadenagara	No	250.0	Rupees Two Hundred Fifty Only
27	66	Rachenahalli	No	250.0	Rupees Two Hundred Fifty Only
28	6	Hire charges compoment name 1087 Crane charges Page No. L Sl No. 66 PWD SR 2018-19 Lifting of Lord Ganesh Hegadenagara	Day	2900.0	Rupees Two Thousand Nine Hundred Only
29	6	Rachenahalli	Day	2900.0	Rupees Two Thousand Nine Hundred Only
30	11	1024 - Hire Charges of Tractor 50 HP including Operator and Fuel (P. XLVIII/I. 20) PWD SR 2018-19 Hegadenagara	Day	1800.0	Rupees One Thousand Eight Hundred Only
31	11	Rachenahalli	Day	1800.0	Rupees One Thousand Eight Hundred Only
32	220	KSRB 2.3 : Filling available excavated earth (excluding rock) in sides of foundations upto plinth in layers not exceeding 20cms, in depth, compacting each deposited layers by ramming after watering with lead upto 50m, and lift upto 1.5m, including cost of all labour complete as per specifications, specification. No. KBS 2.9, Page No. 7 / Item No. 2.10 / PWD SR 2018-19	Cum	180.0	Rupees One Hundred Eighty Only

Shivakumar B S

Signature of the Contractor

9/09

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92

9/09